



**The District Co-operative Central Bank Ltd.,**

(Govt. Partnered Bank)

**MAHABUBNAGAR**

Head Office, #1-6-144/5A# Post Box No.14, Dist. Court Road, Mahabubnagar - 509001, TG.

RBI LICENCE No. RPCD. (H) COOP/20/05.08.03/2011-12

Reg.No. 20942

(Estd 27.03.1920) Email: ceo\_mbnr@mbnrdccb.org Website: <https://dccbmbnr.org>

Ref No: 1112

Date:

Date: 12.06.2025

**TENDER NOTICE**

**Sealed Quotations are invited for Renovation work of Branch  
Building at Branch Wanaparthi, DCCB Mahabubnagar**

**Ref:** Premises/ Renovation work of Branch Building at Branch Wanaparthi /2025-26,

The District Co-operative Central Bank Ltd., Mahabubnagar invites sealed quotations/Bids for Construction of Branch Building Kodangal, DCCB Mahabubnagar as per the specifications provided by the Bank. Quotations to be submitted at: The District Co-operative Central Bank Ltd., H No.1-6-144/5A, Post Box No. 14, District Court Road, Mahabubnagar.

- For more project details log on to <https://dccbmbnr.org>
- Date of for submission of bids/ quotations is **13.06.2025**, time: **10.00 AM**.
- Last date for submission of bids/ quotations is **20.06.2025**, time: **04.00 PM**.
- Bidding Opening date: **21.06.2025**, time: **04.00PM**.
- For queries contact 9912222653
- Bank's decision will be final in the Tender process.

  
12/6/25  
**Assistant General Manager**

MBNR DCCB/Premises/ Renovation work of Branch Building at Wanaparthi  
(Tender)/2025-26.

**Project specifications and other parameters to submit bids for  
Renovation work of Branch Building at Branch Wanaparthy,  
DCCB Mahabubnagar**

1. Application fees of **Rs.5000.00** (nonrefundable), EMD of **Rs.2.5% of the L1 bidder amount** (refundable) must be paid after finalization of Tenders through NEFT or DD in favor of:
    - The District Co-Operative Central Bank Ltd., Mahabubnagar
    - A/c no: **1401201000000004**
    - IFSC Code: **TSAB0014001**
    - Branch: **Head Office, Mahabubnagar**
  2. Period of completion of work: **180** days.
  3. Last date and time for submission of Tenders: **20.06.2025, 04.00PM.**
  4. Date and time of opening of Tenders: **21.06.2025, 04.00 PM.**
  5. Copies of valid contractor/firm registration proceedings, application fees & EMD details shall be enclosed along with the hard copies of Tender documents.
  6. Eligibility Criteria:
    - Class of contractor: Class I to Class V
    - To furnish copy of PAN card
    - The bidder should produce copy of GST<sup>†</sup> registration with commercial tax Department, Telangana State and also produce the list of projects executed in the past two years.
  7. Cement grade: 43 (brick work), 53 (RCC work)
  8. Steel grade: FE 5503
  9. The selected bidder must enter into the agreement as per the terms and conditions Stipulated by the Bank after finalization of Tenders.
  10. The bids submitted are liable to be cancelled if:
    - Furnished false/fabricated particulars in the forms, statements submitted in proof of qualification requirements.
    - Not turned up for entering into agreement when called upon.
- MBNR DCCB/Premises/ Renovation work of Branch Building at Wanaparthy  
(Tender)/2025-26.



- Record of poor progress such as abandoning the work, not properly completing the contract, inordinate delays in completion, litigation history and financial failures etc.,
11. The bidder is advised to visit and examine the Site of work, its surroundings and obtain all information that may be necessary for preparing the Tender for entering into contract for construction work. The costs of visiting the site shall be at the Bidder's own expense.
  12. The construction work should be executed under the supervision of Contract civil Engineer of the Bank.
  13. Banks decision will be final in the Tender process.
  14. The Bank reserves right to cancel or postpone the Tender process any point in time.

  
**Assistant General Manager**

**ABSTRACT ESTIMATION FOR RENNOVATION WORKS OF BANK  
BUILDING (Groundfloor) IN WANAPARTHY(TOWN) AND DISTRICT.**

**BELONGS TO :**      **WANAPARTHY BRANCH-DCCB MAHABUBNAGAR.**

**Date:**

GROUND FLOOR							
Description Of Work	Dimensions			Quantity	Rate	Per unit	Amount
	Length, breadth, depth in meters						
1)9"external wall brick masonry with cement mortar(1:8) In superstructure including all charges of mason work Windows 5'x4'-6no's Doors 8'x10'-2no's	40.24	0.23	3.04	28.13 -2.53 - 3.46=22.14		Cum	
2)4.5 " brick work for toilet	3.04		3.04	9.24		sqm	
3)Supply and placing of design mix M20 grade concrete (1:1.5:3) for Retaining wall for strong room ground floor	23.78	0.23	3.04	16.62- 0.59=16.03		cum	
4)Supply, Fabricating, Placing of (HYSD FE500)Steel bars in retaining walls	8mm 10mm 12mm 16mm	78 lengths 92 lengths 4lengths 4lengths		1175kgs=1.1 75 tonnes		TONNES	
5)Plastering 20mm thick using two coats with cement mortar(1:6) for external walls, parapet wall, ceiling	1x2x56.70 1x2x3.04		3.04 3.04	344.7 18.48 -22.07 -29=311		Sqm	
6)Flooring with 2'x2' double charges tiles anti skidding with side skirting including all labour charges	21.03	7.31		153.72		SQM	



7) Painting external & internal walls with top brand colour and primer will applied before painting for all walls.				311		sqm	
8) Providing Birla wall care putty				155.5		sqm	
Providing false ceiling inside the office to ceiling	21.03	7.31		153.72		sqm	
9) Rolling shutters 2no's of size 8' x 10'-2no's				14.77		sqm	
10) UPVC windows of 3 track of standard quality for finished work 6NO'S	1.52	1.21		11.03		sqm	
11) Iron grills for windows 6 no's				200		kgs	
12) 2 door to east wall aluminum  Thickness 3"x4", size 4'x6'9"				lumpsum			

13) Lump sum amount for Electric work & material of standard ISI mark including all labour charges							
14) Lump sum amount for Plumbing & Sanitary works with material of standard ISI mark including all charges							
15) Dismantling of all brick walls of a south side shutters of a building	35.67 27.43	0.23 0.115	3.04 3.04	24.94 9.58 = 34.52		cum	
					<b>TOTAL</b>		

**GRAND TOTAL (GROUND FLOOR) =**

**TOTAL AMOUNT IN WORDS (),**

ABOVE MENTIONED UNIT RATES DATA IS PREPARED BY FOLLOWING TELANGANA SSR 2024-2025 & LOCAL MARKET RATES .

**Engineer Sign**